



कपिलवस्तु नगरपालिका
KAPILVASTU MUNICIPALITY
नगर कार्यपालिकाको कार्यालय
OFFICE OF MUNICIPAL EXECUTIVE
तौलिहवा, कपिलवस्तु
TAULIHAWA, KAPILVASTU
लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL



पत्र संख्या : ०८०/०८१(पुर्वाधार)

चलानी नं.: १५५१

विषय : दररेट पेश गर्ने सम्बन्धमा।

मिति : २०८०/११/२१

श्री निर्माण व्यवसायीज्युहरु

उपरोक्त विषयमा यस कार्यालयबाट जिल्ला प्रशासन कार्यालयको भवन तथा कम्पाउण्डवालमा रंगरोमन र मर्मत सम्भार कार्य नगरपालिकाको खरीद नियमावली २०७५ को नियम ८५ को उपनियम(१) अनुसार वाताद्वारा गराउनु पर्ने भएकोले यस कार्यालयमा चालु आव.को लागि सुचीकृत निर्माण व्यवसायीहरुले BoQ मा उल्लेखित आइटमका कामहरु के कति दररेटमा गर्न सकिन्छ ? BoQ मा भरी मिति २०८० फाल्गुन २३ गते कार्यालय समय भित्र पेश गर्नु हुन अनुरोध छ ।

गणेश प्रसाद अर्याल

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

बोधार्थ-

श्री सुचना प्रविधि शाखा Website मा Upload गरिदिनुहुन ।



Kapilvastu Municipality
Office of the Municipal Executive
Lumbini Province
Tadaha, Kapilvastu



Bill of Quantity

Name of Project :- जिल्ला प्रशासन कार्यालय भवन मर्मत तथा रंगरोगन कार्य
Address :- कपिलवस्तु नगरपालिका वार्ड न.०१, प्रशासन कार्यालय

२०७३

०११/११

प्रमुख प्रशासकिय अधिकृत

| S.No | Description of works | Quantity | Unit | Rate | | Amount |
|------|---|----------|------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | MS Pipe work including supply of materials,application od red oxide and workmanship complete as per site incharge. | 40.000 | Kg | | | |
| 2 | Repairing work including materials and labour cost all complete. | 1.000 | job | | | |
| 3 | 2" Dia top,1" dia middle and bottom pipe in 4 rows, 2" dia posts at 1m c/c finish clear height. | 2.930 | Rm | | | |
| 4 | Demolition of CGI sheet works including Collection of wood and iron works complete as per site incharge. | 7.160 | Sqm | | | |
| 5 | CGI sheet works including Supply & fitting of CGI Sheet including all j-hooks and other fixures and fittings complete as per site incharge. | 7.160 | Sqm | | | |
| 6 | General false ceiling works including Supplying and fitting of Gypsum board in GI Frame along with all fittings complete as per site incharge. | 7.160 | sqm | | | |
| 7 | Providing and applying Single coat of the approved quality Distemper paint in inner walls and ceiling including the cost of scaffolding; all complete with necessary tools, labours and materials in perfect line and level as per drawings, specifications and instructions of Supervision Engineer. | 1561.380 | Sqm | | | |

कपिलवस्तु नगरपालिका
 नगर कार्यपालिकाको कार्यालय
 तहकिल्ला कपिलवस्तु
 लुम्बिनी प्रदेश
 २०७३

मार्ग
 प्रमुख प्रशासकिय अधिकारी

| | | | | | |
|----|--|---------|-----|------------------------------------|--|
| 8 | Providing and applying two coat of the approved quality Distemper paint in inner walls and ceiling including the cost of scaffolding; all complete with necessary tools, labours and materials in perfect line and level as per drawings, specifications and instructions of Supervision Engineer. | 844.000 | Sqm | | |
| 9 | Providing and applying Single Coat of first quality hundred percent acrylic paint (Apex weatherproof external emulsion or approved equivalent manufactured by Asian Paints, Berger Paints, or ICI.) | 410.820 | Sqm | | |
| 10 | Providing and applying two or more coats of first quality hundred percent acrylic paint (Apex weatherproof external emulsion or approved equivalent manufactured by Asian Paints, Berger Paints, or ICI.) | 611.080 | Sqm | | |
| 11 | Supplying and applying One Coat Enamel Paint Including Primer. | 450.500 | Sqm | | |
| 12 | Painting work of office board including writing work and supplying and application of primer coat and enamel paint including all workmanship and materials and accessories, scaffolding works required for finish the job as instruction given by the site in charge. | 1.00 | LS | | |
| 13 | Project Information Board | 1.00 | LS | | |
| | | | | Total | |
| | | | | VAT @ 13% | |
| | | | | Total with VAT | |
| | | | | Grand Total with VAT and PS | |

निर्माण व्यवसायको नाम :-

ठेगाना :-

सही / छाप :-